

## ORIGINAL ARTICLE

# Physiological and evolutionary studies of NAP systems in *Shewanella piezotolerans* WP3

Ying Chen<sup>1,2,4</sup>, Fengping Wang<sup>1,4</sup>, Jun Xu<sup>1</sup>, Muhammad Aamer Mehmood<sup>1,3</sup>  
and Xiang Xiao<sup>1,2</sup>

<sup>1</sup>Key Laboratory of MOE for Microbial metabolism and School of Life Sciences and Biotechnology, State Key Laboratory of Ocean Engineering, Shanghai Jiao Tong University, Shanghai, China and <sup>2</sup>School of Life Sciences, Xiamen University, Xiamen, China

**Most of the *Shewanella* species contain two periplasmic nitrate reductases (NAP- $\alpha$  and NAP- $\beta$ ), which is a unique feature of this genus. In the present study, the physiological function and evolutionary relationship of the two NAP systems were studied in the deep-sea bacterium *Shewanella piezotolerans* WP3. Both of the WP3 *nap* gene clusters: *nap*- $\alpha$  (*napD1A1B1C*) and *nap*- $\beta$  (*napD2A2B2*) were shown to be involved in nitrate respiration. Phylogenetic analyses suggest that NAP- $\beta$  originated earlier than NAP- $\alpha$ . Tetraheme cytochromes NapC and CymA were found to be the major electron deliver proteins, and CymA also served as a sole electron transporter towards nitrite reductase. Interestingly, a  $\Delta$ *napA2* mutant with the single functional NAP- $\alpha$  system showed better growth than the wild-type strain, when grown in nitrate medium, and it had a selective advantage to the wild-type strain. On the basis of these results, we proposed the evolution direction of nitrate respiration system in *Shewanella*: from a single NAP- $\beta$  to NAP- $\beta$  and NAP- $\alpha$  both, followed by the evolution to a single NAP- $\alpha$ . Moreover, the data presented here will be very useful for the designed engineering of *Shewanella* for more efficient respiring capabilities for environmental bioremediation.**

The ISME Journal advance online publication, 2 December 2010; doi:10.1038/ismej.2010.182

**Subject Category:** evolutionary genetics

**Keywords:** NAP; periplasmic nitrate reductase; *Shewanella*.

## Introduction

Nitrate is the most preferable substrate for bacterial anaerobic respiration because of its high redox potential. There are three types of prokaryotic nitrate reductase comprising of the cytoplasmic assimilatory (NAS), membrane-bound respiratory (NAR) and periplasmic dissimilatory (NAP) nitrate reductase used for nitrate respiration (Moreno-Vivian *et al.*, 1999, Richardson *et al.*, 2001, Stolz and Basu, 2002). All of them contain a molybdenum cofactor at their active sites; however their location, structure, sequence and terminal products are different. The distribution and physiological functions of NAS, NAR and NAP are different in different organisms. Many bacteria can express not only one functionally nitrate reductases,

and they usually have important physiological roles. For example, *Escherichia coli* harbors two NARs and one NAP. The first NAR serves at high nitrate concentration (Potter *et al.*, 1999), the second NAR is expressed in response to stress and is part of the RpoS regulon (Spector *et al.*, 1999); and the NAP enzyme is primarily expressed at low nitrate concentrations, and assists the nitrate respiration via NAR, in which bioenergetic efficiency is limited (Stewart *et al.*, 2002). *Paracoccus pantaotrophus* contains NAS, NAR and NAP, and each of them serves different functions (Sears *et al.*, 1997, Tabata *et al.*, 2005).

At present, the availability of a large number of microbial genomes has made it possible for us to get insight view of the distribution and evolution of prokaryotic nitrate reductase. A recent review of the genomes of 19 *Shewanella* strains shows that most of the *Shewanella* contain two types of NAP: NAP- $\alpha$  and NAP- $\beta$  (Simpson *et al.*, 2010). Considering the unparalleled capability of *Shewanella* to utilize a variety of substrates, the presence of two NAPs may reflect an adaptation of *Shewanella* to cope with the various environmental conditions. There are several implications for this special feature of *Shewanella* genus: (1) The excess *nap* gene cluster may not be expressed, similarly as the two dimethylsulfoxide reductase gene clusters in *S. oneidensis* MR-1

Correspondence: X Xiao, Key Laboratory of MOE for Microbial metabolism and School of Life Sciences and Biotechnology, State Key Laboratory of Ocean Engineering, Shanghai Jiao Tong University, 800 Dongchuan road, Mulan building, Shanghai 200240, China.  
E-mail: xoxiang@sjtu.edu.cn

<sup>3</sup>Present address: Department of Bioinformatics & Biotechnology, GC University, Faisalabad, Pakistan.

<sup>4</sup>These authors contributed equally to this paper.

Received 22 June 2010; revised 7 October 2010; accepted 31 October 2010

(Gralnick *et al.*, 2006); (2) The two NAP systems may have distinct physiological functions such as NAP- $\alpha$  may serve in denitrification or redox balancing (Simpson *et al.*, 2010); (3) The double copy of *nap* gene are functionally redundant. Besides all these possibilities, it is still an open question that what is the evolutionary relationship of the two NAPs? And why it happens only in *Shewanella* genus?

Generally the basic components of NAP are *napDABC*. The cytoplasmic protein NapD is involved in NapA relocation by binding to the NapA twin-arginine signal peptide (Maillard *et al.*, 2007). The NapAB form heteromeric complex catalyses by the reduction of nitrate to nitrite. The electrons from quinol pool are generally passed through one or two cytochrome-*c* containing proteins (NapC and NapB (di-*c*-haem cytochrome redox partner of NapA)) to the catalytic subunit, NapA that contains a Mo-bis-molybdopterin guanine dinucleotide cofactor and a cluster. The NapC is a tetrahaem *c*-type cytochrome of the NapC/NirT family, consists of ~175 amino acid residues that are assumed to form an N-terminal membrane-spanning helix and a globular cytochrome-*c* domain situated at the outside of the bacterial membrane (Gross *et al.*, 2005).

A review of 136 species across 51 genera shows that most of the *nap* gene clusters contain *napC*. In the *napC* free strains, such as *Campylobacter jejuni* and *Wolinella succinogenes*, NapGH are at the substitution place of NapC (Pittman *et al.*, 2007, Kern and Simon, 2008). In *E. coli*, which contains NapGH and NapC, NapGH is not involved in menaquinol oxidation and instead form a quinol

dehydrogenase that transfers electrons from ubiquinol through NapC to NapAB (Brondijk *et al.*, 2002, 2004). In the well-studied *S. oneidensis* MR-1, which also doesn't have a *napC* gene, CymA has key roles in both nitrate and nitrite reduction (Murphy and Saltikov, 2007; Gao *et al.*, 2009). CymA is also a tetrahaem *c*-type cytochrome belonging to NapC/NirT family, and it has been proven to be the essential electron transport protein in 4–6 pathways studied in *Shewanella* (Myers and Myers, 2000, Murphy and Saltikov, 2007). As most of the *Shewanella* strains contain both a *napC* dependent and a *napC* independent *nap* gene clusters, it is crucial to study and distinguish the roles of NapC and CymA in the electron transport in *Shewanella*.

In the present study, we investigated the two NAP systems in *Shewanella* by using a combination of bioinformatics, genetic and phylogenetic analyses using *S. piezotolerans* WP3 as a model organism. The strain WP3 was isolated from 1.9 km depth marine sediment in west Pacific Ocean and its whole genome has been sequenced (Xiao *et al.*, 2007, Wang *et al.*, 2008). Two *nap* gene operons are identified in WP3 genome: *napDABC* (*swp\_2775-2772*) and *napDAB* (*nap\_4456-4458*). Here, we show that both NAPs are functional in anaerobic nitrate respiration, and NAP- $\alpha$  confers a selective advantage to WP3 in nitrate utilization. On the basis of the data presented, we have proposed an evolutionary scenario of NAPs in *Shewanella*: NAP- $\beta$  as the prototype at beginning, then NAP- $\alpha$  was obtained to form the dual NAP system containing both NAP- $\alpha$  and NAP- $\beta$ , and finally would evolve to a single NAP- $\alpha$ .

**Table 1** Strains and plasmid

Strain or plasmid	Description	Reference or source
<i>E. coli</i> strain WM3064	Donor strain for conjugation; $\Delta$ dapA	Gao <i>et al.</i> (2006)
<i>S. piezotolerans</i> WP3 strains		
WT	Wild type	Lab stock
$\Delta$ napA1	<i>napA1</i> deletion mutant derived from WP3	This study
$\Delta$ napA2	<i>napA2</i> deletion mutant derived from WP3	This study
$\Delta$ napA1 $\Delta$ napA2	<i>napA1</i> and <i>napA2</i> double deletion mutant derived from WP3	This study
$\Delta$ napC	<i>napC</i> deletion mutant derived from WP3	This study
$\Delta$ cymA	<i>cymA</i> deletion mutant derived from WP3	This study
$\Delta$ napA1 $\Delta$ cymA	<i>napA1</i> and <i>cymA</i> double deletion mutant derived from WP3	This study
$\Delta$ napA2 $\Delta$ napC	<i>napA1</i> and <i>napC</i> double deletion mutant derived from WP3	This study
$\Delta$ napC $\Delta$ cymA	<i>napA1</i> and <i>cymA</i> double deletion mutant derived from WP3	This study
Rc- $\Delta$ cymA-cymA	strain $\Delta$ cymA with pSW1-cymA	This study
Rc- $\Delta$ napC $\Delta$ cymA-cymA	strain $\Delta$ napC $\Delta$ cymA with pSW1-cymA	This study
Plasmid		
pRE112	Allelic-exchange vector	Edwards <i>et al.</i> (1998)
pRE112-napA1	pRE112 containing the PCR fragment for deleting <i>napA1</i>	This study
pRE112-napA2	pRE112 containing the PCR fragment for deleting <i>napA2</i>	This study
pRE112-napC	pRE112 containing the PCR fragment for deleting <i>napC</i>	This study
pRE112-cymA	pRE112 containing the PCR fragment for deleting <i>cymA</i>	This study
pSW2	Chl R, derivative from filamentous bacteriophage SW1; used for complementation	Unpublished work in our lab
pSW1-cymA	pSW1 containing <i>cymA</i> and upstream promoter region from WP3	This study

**Table 2** Primers

Primer	Sequences 5'-3'	Description
<i>Mutation use</i>		
swp2774up1	AAGAGCTCAGCAAACCCATAAATAGC	deleting <i>napA1</i>
swp2774up2	CAGTTGCACAAATGCTTGATCCCAGCTTACAG	deleting <i>napA1</i>
swp2774do1	AGCATTTGTGCAACTGATCCACTATCGAAACA	deleting <i>napA1</i>
swp2774do2	AATCTAGACGTGAGTTTATCAAAGCAAATGC	deleting <i>napA1</i>
swp4457up1	GCGAGCTCGAACCAAGAATTTTCATATTAC	deleting <i>napA2</i>
swp4457up2	AGTTTCAAAAATGCTATCTTTTGTCTGCGAGC	deleting <i>napA2</i>
swp4457do1	ATAGCATTTTGAACATAAAGGCCGTAACAAGC	deleting <i>napA2</i>
swp4457do2	CGTCTAGAGCTGCTCGAAATATCAGTGATC	deleting <i>napA2</i>
swp4806up1	AAGGTACCCCTCCTAAAATCTGACCG	deleting <i>cymA</i>
swp4806up2	CAGTTAAGGGTGTGCTCACGTTTACCCAAAG	deleting <i>cymA</i>
swp4806do1	GCAACACCCTTAACCTGGGTTGTGGGTAAGTG	deleting <i>cymA</i>
swp4806do2	AATCTAGAGAGAGAGTTAGAGCCATGTCTCAT	deleting <i>cymA</i>
swp2772up1	AAGAGCTCATACTGATGGTATAAATGACAAAAC	deleting <i>napC</i>
swp2772up1	TGCTGGCGCGAAGTAGAAGGTTGGCAATAAGGA	deleting <i>napC</i>
swp2772do1	CTACTTCGCGCCAGCAAACCCATAAATAGCA	deleting <i>napC</i>
swp2772do2	AATCTAGACGGCGACACTGAGCTAGAAA	deleting <i>napC</i>
<i>RT-PCR use</i>		
napC-S	CAACATTCTACCGCACTTGA	RT-PCR
napC-R	GGCGATCCCTTTATGGCAAT	RT-PCR
napB1-S	CGGCGACACTGAGCTAGAAAC	RT-PCR
napB1-R	GCGCGCACTTTCTTCA	RT-PCR
napA1-S	CATGGATTATTTTCAGCGCCTTAT	RT-PCR
napA1-R	CCACAGTTGTGTTCTTCATCAG	RT-PCR
napD1-S	TGTGCTTACCTGAGGCTCATATTTTC	RT-PCR
napD1-R	AGTTTGGCTTAAGTGCTCTGGACTA	RT-PCR
napD2-S	CGTTGTCTGCCCTTGTGG	RT-PCR
napD2-R	CAAACTTTCCTTCATCGGTAACG	RT-PCR
napA2-S	AACCGGCCAGCCATCA	RT-PCR
napA2-R	GATGAGCAAAGGTACCGCACTTCA	RT-PCR
napB2-S	TCACAGTCCAGCAAAAAGCAAA	RT-PCR
napB2-R	GCAAAGTGGCAAGGGTCGAT	RT-PCR
cymA-S	ACTGGCGAGCACTTTTTAAACC	RT-PCR
cymA-R	CCGACGACTAGTAATGCCAGAA	RT-PCR
<i>Complementation use</i>		
RC-cymA-F	CGGGATCCAGACCCACCTTTTGAGGAAA	complement <i>cymA</i>
RC-cymA-R	CCGCTCGAGTCCACTTCTGCTTTGCATTG	complement <i>cymA</i>
<i>Competition assay use</i>		
P-napA2-F	CAACAACATGCAAGCGGGTC	To amplify deletion region
P-napA2-R	ACCGCGACCAAATTGAGCAT	To amplify deletion region

Abbreviation: RT-PCR, reverse transcription-PCR.

## Materials and methods

### *Bacterial strains, media and culture conditions*

All bacterial strains and plasmids used in the present study are listed in Table 1. The *Shewanella* strains were cultured in marine broth medium 2216E at 20 °C. The *E. coli* strain WM3064 was incubated in Luria-Bertani medium (Trypton: 10 gl<sup>-1</sup>, yeast extract: 5 gl<sup>-1</sup>, NaCl: 10 gl<sup>-1</sup>) at 37 °C. Chloramphenicol (25 µg ml<sup>-1</sup> for *E. coli*; 12.5 µg ml<sup>-1</sup> for WP3) was added to the medium when required.

A modified 2216E medium (Trypton: 5.0 gl<sup>-1</sup>, Yeast extract: 1.0 gl<sup>-1</sup>, NaCl 34 gl<sup>-1</sup>, D-L lactate: 20 mM, pH = 7.0) supplemented with sodium nitrate was used for physiological characterization of the mutant under anaerobic condition. The OD600 was measured using a SHIMADZU UV-2550 spectrophotometer (SHIMADZU CO., Kyoto, Japan) to draw growth curve. The LML medium (Cruz-Garcia *et al.*, 2007) was also used in case.

For anaerobic cultivation, a modified method was used (Miller and Wolin, 1974; Balch and Wolfe, 1976). Briefly, media that didn't contain any electron acceptor were prepared under non-sterile condition. Then the media were dispensed into serum bottles gassed with O<sub>2</sub>-free nitrogen, and the stoppers were inserted as the bottles were withdrawn from gassing needles. Metal seals were then crimped to seal the caps, and then the media were autoclaved with a needle inserted into the stopper. When the autoclave was done, the needles were plucked off immediately. After the media were cooled, the serum bottles were gassed by a gassing manifold system (Balch and Wolfe, 1976). Nitrate solution (0.4 M, sodium nitrate) was filter sterilized in a vinyl anaerobic airlock chamber (Coy Laboratory Products Inc., Grass Lake, MI, USA) and added to the concentration needed. The serum bottles, stoppers and metal seals were bought from Wheaton Science Products (Millville, NJ, USA).

### Development of the mutant strains

The genes *napA1*, *napA2*, *napC* and *cymA* were deleted in-frame using a fusion PCR method with plasmid pRE112 as described earlier (Wang *et al.*, 2009). The primers used for generating PCR products for mutagenesis are listed in Table 2. To construct a *napA1* in-frame deletion mutant, two fragments flanking *napA1* were amplified by PCR with primers swp2774up1 and swp2774up2, primers swp2774do1 and swp2774do2, respectively. The fusion PCR products were generated by using the amplified fragments as templates with primers swp2774up1 and swp2774do2, and ligated into the *Sac I* and *Xba I* site of plasmid pRE112. This resulted in plasmid pRE112-*napA1* and was first transformed into *E. coli* WM3064 by calcium chloride transformation and then into WP3 by conjugation. Integration of the mutated version of *napA1* into the chromosome was selected by chloramphenicol resistance and further confirmed by PCR. The verified transconjugants were grown in 2216E broth in the absence of NaCl and plated on 2216E medium supplemented with 10% of sucrose. The chloramphenicol-sensitive and sucrose-resistant colonies were screened by PCR for the deletion of *napA1*.

The same strategy was used for constructing *napA2*, *napC* and *cymA* in-frame deletion mutants with primers listed in Table 2. Double mutant  $\Delta napA1\Delta napA2$  was constructed either by introducing pRE112-*napA2* into the  $\Delta napA1$  or by introducing pRE112-*napA1* into the  $\Delta napA2$ . Same strategy was used to construct  $\Delta napA1\Delta cymA$ ,  $\Delta napA2\Delta napC$  and  $\Delta napC\Delta cymA$ , respectively.

### Complementation assay of the mutant

For complementation, we used a *Shewanella*-*E. coli* shuttle plasmid vector pSW2 developed from the filamentous phage SW1 of WP3 (Wang *et al.*, 2007, our unpublished data). To introduce *cymA* gene into the  $\Delta cymA$  mutant, *cymA* along with its native promoter region was amplified by PCR using WP3 genomic DNA as the template and primers RC-*cymA*-F and RC-*cymA*-R as listed in Table 2. The PCR product and pSW2 were digested with both *BamH I* and *Xho I*, respectively, and then ligated to generate pSW2-*cymA*. The plasmid was introduced into WM3064 by calcium chloride transformation then mobilized into  $\Delta cymA$  by mating. The same strategy was used to construct complementing strain for  $\Delta napC\Delta cymA$ .

### RNA extraction and reverse transcription

The total RNA from cells was extracted as described previously (Wang *et al.*, 2009). Total RNA was isolated from the mid-log phase ( $OD_{600} \approx 0.2$ ) cells culture growing at different conditions with TRI reagent-RNA/DNA/protein isolation kit (Molecular Research Center Inc., Cincinnati, OH, USA) following the manufacturer's instructions. The RNA samples were treated with DNase-I at 37 °C for 1 h and then

purified with RNeasy Mini Kit (Qiagen, Hilden, Germany). The purified RNA samples were used to synthesize complementary DNA with the RevertAid First Strand cDNA Synthesis Kit (Fermentas, Burlington, ON, Canada) following the manufacturer's instructions.

### Real-time PCR

The primer pairs (Table 2) for the selected genes for real-time PCR were designed using Primer Express software (Applied Biosystems, Foster City, CA, USA). The PCR was performed using 7500 System SDS software in reaction mixtures with total volumes of 20  $\mu$ l containing 10  $\mu$ l SYBR green-I Universal PCR Master Mix (Applied Biosystems, Warrington, UK), 0.5  $\mu$ M each primer and 1  $\mu$ l complementary DNA template. The amount of target was normalized to that of the reference gene swp\_2079, whose expression remains stable under various conditions relative to the calibrator (the transcription levels of the genes at aerobic condition, nitrate free medium, 20 °C, were set as 1). The real-time reverse transcription-PCR assays were performed in triplicate for each sample, and a mean value and standard deviation were calculated for the relative RNA expression levels.

### Determination of nitrite concentrations in culture


The 5  $\mu$ l of the culture supernatants from anaerobic growth experiments were diluted to 250  $\mu$ l with deionized water, then added with 500  $\mu$ l 1% (w/v) sulphanilamide (Bio Basic Inc., Markham, ON, Canada) dissolved in 25% (v/v) HCl and 500  $\mu$ l of 0.2% (w/v) 1-naphthylamine dissolved in 25% (v/v) acetic acid, successively. After 40 min, the absorbance at 540 nm was measured using a SHIMADZU UV-2550 spectrophotometer, and nitrite concentrations were determined in comparison with the standard curve.

### Competition assay

The competition assay was performed as described previously (Gao *et al.*, 2009). Anaerobic cultures of wild type and  $\Delta napA2$  were grown independently to stationary phase in modified 2216E medium supplemented with 2 mM sodium nitrate to  $OD_{600}$  at 0.3. And competition assay was performed in 4 mM nitrate concentration. Primers used for scanning were listed in the Table 2. Relative fitness, *W*, was calculated as described earlier (Lenski *et al.*, 1991).

### Constructing the phylogenetic tree

The phylogenetic tree (Figure 1) contains 37 NapA protein sequences from 21 genomes of *Shewanella* species. The phylogenetic tree in Figure 2 contains 183 NapA sequences, which are mainly from those previously described (Simpson *et al.*, 2010), in addition we added the NapA of *S. violacea* DSS12,



**Figure 1** Phylogenetic tree of NapA protein sequences of *Shewanella*. NapA1 of WP3 belongs to Nap- $\alpha$ -1; NapA2 belongs to Nap- $\beta$ , and the other NapC containing NAP is in the Nap- $\alpha$ -2 group. We use NapA of *E. coli* as the out-group by the method of MrBayes.

*S. benthica* KT99, and monomeric NAS of *Bacillus subtilis*, *Klebsiella oxytoca*, *Rhodobacter capsulatus* and *Synechococcus elongatus*. We used formate dehydrogenase protein of *Bacillus cereus* as the out-group, as formate dehydrogenase also belongs to DMSO (dimethyl sulfoxide) reductase family protein. The protein sequences were multiply aligned by ClustalW (Thompson *et al.*, 1999), using BLOSUM matrix, with the gap open cost 7 and gap extend cost 0.1. Then posterior tree was performed by the methods of MrBayes (Huelsenbeck and Ronquist, 2001) with equal rate variation. The posterior probabilities were used as measures of statistical support for the branches. All these processes were performed by using the software Geneious 4.8.3 (Biomatters Ltd., Auckland, New Zealand) (Drummond *et al.*, 2010) along with the ClustalW 2 and the MrBayes 3.1.2. GenPept accession numbers of NapA protein sequences used for Figures 1 and 2 and are listed in Supplementary information Table S1.


## Results

### Evolutionary relationships of NAPs

A phylogenetic tree of NapA proteins from 21 genomic sequences of *Shewanella* (sequence obtained from NCBI GenPept) was constructed as shown in Figure 1. On the basis of the phylogenetic

analysis, the NapA orthologous in the genus *Shewanella* could be divided into NAP- $\beta$  and NAP- $\alpha$  as suggested previously (Simpson *et al.*, 2010). The NAP- $\alpha$  cluster could be further divided into two subclusters: Nap- $\alpha$ -1 and Nap- $\alpha$ -2. The Nap- $\alpha$ -1 group includes NAPs from *S. violacea*, *S. benthica*, *S. sediminis* and *S. piezotolerans*, all of which are psychrophilic/psychrotrophic. In the genomes of the compared *Shewanella* strains, dual NAP system consisting of NAP- $\beta$  and either Nap- $\alpha$ -1 or Nap- $\alpha$ -2 is the major genotype, although sole NAP- $\beta$  (*S. oneidensis* and *S. halifaxensis* HAW-EB4) or sole NAP- $\alpha$  (*S. denitrificans*, *S. violacea* and *S. benthica*) is the minor genotype.

The evolutionary relationships of *Shewanella* NAPs and other known NAPs were carefully analyzed by constructing a robust phylogenetic tree containing 186 NapA proteins from 165 different organisms of 53 genera (Figure 2). The tree has three major branches: ‘Branch 1’ is comprised of NAP- $\beta$  including the monomeric NAP subclass that does not contain NapB, but instead contains a NapM, NapG or predicted protein as redox partners. ‘Branch 2’ is generally comprised of NAP- $\beta$  from enterobacteriaceae family bacteria, and only the members near *Yersinia* belong to NAP- $\alpha$ . ‘Branch 3’ has large population of NAP- $\alpha$ , with only NAP- $\beta$  of *Shewanella* and *Aeromonas* nearby branch root. The tight NapAB interaction subgroup and monomeric NAP subgroup are highlighted in the tree. The tight



**Figure 2** Phylogenetic tree of bacterial NAPs. The tree contains 185 NapA protein sequences, which come from the genomes of 165 prokaryotes across 53 genera and 4 monomeric Nas. We use formate reductase of *Bacillus* as out-group using MrBayes method. Name abbreviations: Cam, *Campylobacter jejuni*; Wol, *Wolinella succinogenes*; Sul, *Sulfurovum*; Nau, *Nautilia profundicola*; Kle, monomeric Nap of *Klebsiella oxytoca*; Des, monomeric Nap of *Desulfovibrio desulfuricans*; Din, *Dinoroseobacter shibae*; Dec, *Dechloromonas aromatica*; Mag, *Magnetospirillum magneticum*; Hae, *Haemophilus*; Man, *Mannheimia succiniciproducens*; Ser, *Serratia proteamaculans*; Yer, *Yersinia*; Pec, *Pectobacterium atrosepticum*; Cit, *Citrobacter koseri*; Sal, *Salmonella*; Esc, *Escherichia*; Shi, *Shigella*; Aer, *Aeromonas*; Pho, *Photobacterium profundum*; She Nap- $\alpha$ -1, Nap- $\alpha$ -1 group of *Shewanella* genus; Vib, *Vibrio*; She Nap- $\alpha$ -2, Nap- $\alpha$ -2 group of *Shewanella* genus; Sac, *Saccharophagus degradans*; Bra, *Bradyrhizobium* sp.; Pse, *Pseudomonas*; Azo, *Azoarcus* ap. BH72; Bor, *Bordetella bronchiseptica*; Ral, *Ralstonia*; Sin, *Sinorhizobium meliloti*; Rho, *Rhodospirillum centenum*; She Nap- $\beta$ , Nap- $\beta$  group of *Shewanella* genus.

NapAB interaction subgroup is widely accepted as a more evolved group, and monomeric NAP is the evolutionary link from NAS to NAP (Jepson *et al.*, 2006). The Nap- $\alpha$ -1 of *Shewanella* forms a close cluster with those from *Vibrio* species, while the NAP- $\alpha$ -2 forms a relatively independent branch. It is also noticed that the NapC containing NAP accounts for a large proportion of NAP, while the NapC free NAP (Tagged with \*) only contains two parts: the monomeric NAP with its nearby members and the NAP- $\beta$  of *Shewanella*.


#### NAP operons in *S. piezotolerans* WP3

According to the original annotation of WP3 whole genome, there are two sets of genes encoding NAP: *napDABC* (*swp\_2772-2775*) and *napDAB* (*swp\_4456-4458*). We named them as WP3-*nap- $\alpha$*  (*napD1A1B1C1*) and WP3-*nap- $\beta$*  (*napD2A2B2*) (Figure 3). Besides NAP, none of the other nitrate reductase was identified in WP3. Five putative nitrite reductase


(*nrfA*) genes were identified: *swp\_3958*, *swp\_0919*, *swp3403*, *swp\_0614* and *swp\_0613*, and no other genes belonging to *nrf* family were found. Moreover, the genome of WP3 was analyzed for the presence of NirS (cytochrome cd1 nitrite reductase) and NirK (copper-containing nitrite reductase), which catalyze nitrite reduction in denitrification pathway, but none of them were found in the genome. In addition, the gene encoding CymA tagged as *swp\_4806* was found. The blast (McGinnis and Madden, 2004) analyses showed that NapA1 protein sequences share 71% identities with NapA2 and, 94, 85 and 73% identities with that of NAP- $\alpha$  of *S. sediminis* HAW-EB3, *Vibrionales bacterium* and *S. woodyi* ATCC 51908, respectively.

#### Nitrate respiration in WP3

The 2216E medium supplemented with lactate and sodium nitrate was used to study the anaerobic nitrate respiration of WP3, the time course of nitrite



**Figure 3** The *nap* gene operons and their surrounding genes in *S. piezotolerans* WP3. *Nap-α*(*napD1A1B1C*) and *nap-β*(*napD2A2B2*).



**Figure 4** Growth of *S. piezotolerans* WP3 in nitrate medium and the time course of nitrite concentration. (a) Growth curve of WP3 under different nitrate concentrations (0.5, 2, 4, 6 mM). (b) Time course nitrite concentration of WP3 grown in 4 mM nitrate. Data are averages of triplicate cultures.


concentration was monitored along with the cell density in the medium. The growth curve of WP3 in different nitrate concentration ranging from 0.5–6 mM is presented in Figure 4a. The cultures with 2 mM nitrate were shown to have the shortest time to reach the stationary phase, and the cultures with 4 mM nitrate showed highest cell density at stationary phase. Together with the time course curve (Figure 4b), it was observed that nitrite reached a maximum and then decreased due to its reduction to ammonia. The growth curve did not reach to the stationary phase until the nitrite was completely consumed. This phenomenon indicates that the toxin of nitrite will limit cell growth, and the reduction of nitrite is the major process to generate ATP during nitrate respiration.

#### Transcription assays of the two *nap* gene operons


To get a hint if the two NAP systems in WP3 are functional, transcriptional assays of the two *nap* operons were performed by reverse transcription-PCR. The cells were incubated in medium supplemented with 2 mM sodium nitrate and 20 mM lactate anaerobically at 20 °C for RNA extraction (see the Materials and methods). Meanwhile, the transcription patterns of the two NAP operons were also assessed at 4 °C in accord with the most common environmental temperature of the deep-sea sediment where WP3 was isolated. Both the WP3-*nap-α* and WP3-*nap-β* gene clusters were induced by nitrate, and the expression level of *napA2B2* is much higher than that of *napA1B1* (60 folds vs 2 folds induction) (Figure 5). Interestingly at 4 °C, *napA1B1* was highly upregulated (10 folds) comparing with its expression at 20 °C, whereas the expression of *napA2B2* was downregulated by low temperature. These data suggested that the two *nap* operons have different regulatory mechanisms.

#### Both *NapA1* and *NapA2* are functional

The *napA* genes were disrupted to confirm whether both of the *nap* gene operons are functional or not. The mutant  $\Delta napA1$  or  $\Delta napA2$  still showed nitrate-reducing ability, but the double deletion mutant  $\Delta napA1\Delta napA2$  lost the ability of nitrate reduction and could not survive on nitrate (Figure 6a). Therefore, it was confirmed that both of the *nap* gene clusters are functional. In the medium with 2 mM sodium nitrate, the growth and time course nitrite concentration of  $\Delta napA1$ ,  $\Delta napA2$  and the wild-type WP3 seem to have no difference (Figures 6a and c). As the WP3 culture grown at 4 mM nitrate has shown the highest cell density at stationary phase (Figure 4a), the mutated strains were also incubated at nitrate concentration of 4 mM. Surprisingly, the  $\Delta napA2$  strain showed faster growth than both the mutant  $\Delta napA1$  and the WT, and it had higher cell density at stationary phase than the other two strains (Figure 6b). The nitrite in the culture of  $\Delta napA2$  is also the first to exhaust (Figure 6d). However, nearly no difference was observed between the WT and the  $\Delta napA1$  mutant, no matter on growth rate or in time course nitrite concentration. Similar results were obtained when the strains were



**Figure 5** Transcription levels of *nap* genes. The gene transcription of WP3 cells incubated in 2216E medium (2 mM sodium nitrate, anaerobic) was monitored by reverse transcription-PCR as described in the Materials and methods. The pattern of the columns represents different incubating conditions. All the data were normalized to 20 °C aerobic growth without nitrate. Data are averages of triplicate experiments.



**Figure 6** Growth of WP3 wild type and mutant strains on nitrate under anaerobic condition (a, b), and corresponding time course nitrite concentration (c, d). In all panels (●) *ΔnapA1ΔnapA2*; (▲) *ΔnapC*; (■) *ΔnapA2*; (○) *ΔnapA1* and (△) WT are common. (a) Growth on 2 mM nitrate. In this panel, *ΔnapA1ΔnapA2* cannot grow, and in (c) no nitrite was detected. In both (a, c) *ΔnapA1 = ΔnapA2 = WT*, (b) Growth on 4 mM nitrate and corresponding nitrite concentration (d). In both (b, d) *ΔnapA1 = WT*. Data are averages of triplicate cultures.

grown in LML medium (Cruz-Garcia *et al.*, 2007) with 4 mM sodium nitrate (data not shown). These results suggest that the genotype of *ΔnapA2* is more adapted for nitrate respiration.

#### *ΔnapA2* has competitive advantage

A growth competition assay was performed between the mutant *ΔnapA2* and the WT. It was observed

that 90% of the growth was occupied by the mutant *ΔnapA2* after five times transfer (Table 3). In T0 samples, the average number of colonies was 356, of which 49% were the mutant *ΔnapA2* (100 colonies per plate were examined by colony PCR). After 1-day incubation, the number of the *ΔnapA2* increased to 63%. After 5 days, the *ΔnapA2* contributed up to 94 % of the total population. The

relative fitness values of *ΔnapA2* vs WT from T1 vs T0, T5 vs T0 and T5 vs T1 were 1.1301, 1.1335 and 1.1344, respectively. These data suggest that *ΔnapA2* has a competitive advantage in nitrate respiration.

#### Role of *NapC* and *CymA* in nitrate utilization

The mutant strain *ΔnapC* showed growth deficiency as compared with the WT, *ΔnapA2* and *ΔnapA1*, independent of nitrate concentrations (2 or 4 mM) (Figures 6a and b), and it took more time for the nitrite consumption (Figure 6d). The mutant *ΔnapA1* and WT have shown no phenotypic difference when grown in nitrate medium. These data demonstrate that *NapC* is an indispensable part of NAP systems in WP3, the function of *NapA1* could be fully compensated by *NapA2*, but the function of *NapC* cannot be fully compensated by other electron transport proteins.

As the WP3-*nap-β* gene cluster doesn't have *napC*, so the *CymA* is supposed to have the role of *NapC*. A *ΔcymA* mutant and a *ΔnapCΔcymA* were developed and their phenotypes were observed (Figures 7a and b). The growth of *ΔcymA* mutant was significantly decreased in the nitrate media, and maximum growth could be measured up to OD<sub>600</sub> 0.1 whereas the cell density of wild-type WP3 could reach to 0.3 OD<sub>600</sub> units. Meanwhile, the double gene mutant *ΔnapCΔcymA* showed very poor growth (cell density of 0.04 OD<sub>600</sub> units), and traces of nitrite were detected in the culture. These data suggest that both *NapC* and *CymA* are involved in

nitrate reduction, and *CymA* is the sole electron transfer protein between quinol pool and nitrite reductase. The *cymA* gene was cloned into plasmid pSW2 (a *Shewanella-E. coli* shuttle vector constructed in our lab, see Materials and methods) to perform complementation assay for the further confirmation of this phenomenon. It was observed that the ability of nitrite reduction of mutant *ΔcymA* was partially restored by the plasmid harboring *cymA* gene. When the same plasmid carrying the *cymA* gene was transformed into the double mutant *ΔnapCΔcymA*, the reducing abilities of both nitrate and nitrite were partially restored (data not shown).

#### Electron transport preference of *NapC* and *CymA*

To test whether *NapA2* can acquire electron from *NapC* and whether *CymA* can transfer electron to *NapA1*, mutants *ΔnapA1ΔcymA* and *ΔnapA2ΔnapC* were developed. Interestingly, both the mutants were shown to retain the nitrate reducing ability (Figures 7a and b). It indicates that *NapA1* and *NapA2* can acquire electron for nitrate reduction from both *NapC* and *CymA*. However, the nitrate reducing ability of *ΔnapA1ΔcymA* mutant is much lower than the *ΔcymA* mutant (Figures 7a and b), which suggests that electron flow from *NapC* to *NapA2B2* is not as efficient as from *NapC* to *NapA1B1*. On the other hand, the electron flow efficiency from *CymA* to *NapA1B1* is nearly the same as that from *CymA* to *NapA2B2*. These data indicate that *CymA* transport electron to both *NapABs* unspecifically, and *NapC* prefers to transport electrons to *NapA1B1*.

**Table 3** Relative fitness of strains as measured by competition assays

Sample	Number of colonies	WT <sup>a</sup> (%)	<i>ΔnapA2</i> <sup>a</sup> (%)	Relative fitness
T0	356 ± 28	51	49	1.1301 ± 0.0195
T1	369 ± 37	37.33	62.67	1.1335 ± 0.0161
T5	327 ± 37	6.33	93.67	1.1344 ± 0.0183


Abbreviation: WT, wild type.

<sup>a</sup>The averaged percentage of either the wild type or mutant colonies identified by PCR (100 colonies per plate).


## Discussion

#### Electron transport chain in nitrate ammonification of WP3

Based on the above experimental data and current knowledge on nitrate respiration, an electron transport pathway of nitrate ammonification for WP3 is depicted at Figure 8a. The nitrate was reduced to ammonia by a two-step process, in which nitrite



**Figure 7** (a) Growth of WP3 wild type and mutants on 2 mM sodium nitrate under anaerobic condition and (b) corresponding time course nitrite concentration curve. In both panels, (●) *ΔnapCΔcymA*, (▲) *ΔnapA2ΔnapC*, (■) *ΔnapA1ΔcymA*, (○) WT, (▽) *ΔcymA* and (●) *ΔnapA1ΔnapA2* are common. *ΔcymA* can reduce nitrate to nitrite, but cannot further reduce nitrite. The cell density of *ΔcymAΔnapA1* sustains at a low level, and the nitrite accumulation is very slow. *ΔnapCΔcymA* only have a low level of cell density, and trace amount of nitrite can be detected in its culture. In both (a, b) WT = *ΔnapA2ΔnapC*. Data are averages of triplicate cultures.



**Figure 8** Electron transport model for nitrate ammonification. (a) In wild-type WP3, electrons transfer from menaquinol (MKH<sub>2</sub>) to periplasmic nitrate reductase NapAB by NapC and CymA. NapB serves as a direct electron transfer to NapA without catalytic function. When nitrate is exhausted electron will be transferred to nitrite reductase NrfA by CymA directly. (b) In the absence of NapA2, CymA can transfer electron to NrfA specially. (c) In  $\Delta napC$  mutant strain, nitrate reduction is less efficient than WT. (d) In  $\Delta napA1$  mutant, because enzyme activity of NapA1 can be compensated by NapA2, the deletion of *napA1* gene will not affect the growth. Solid lines between proteins represent electron flows. Dash lines in (a, d) indicate that electrons may be transferred from NapC to NapA2, this transferring pathway has been observed in the absence of NapA1 and CymA. Thin line in (c) indicates that the efficiency of this electron transfer may be reduced in the absence of NapC. Thick arrow in (b) indicates that the efficiency of the electron flow from this pathway may be higher in the mutant.

reduction would not start until nitrate was used up (Cruz-Garcia *et al.*, 2007). As shown in the model, NapC and CymA transferred electrons from menaquinol to both NapA1B1 and NapA2B2, and NapC preferentially transfers electrons to NapA1B1. When nitrate was completely consumed, CymA delivers electrons to NrfA directly, and CymA is the sole electron transport protein to NrfA. Five putative *nrfA* genes were found in WP3 genome, but only one gene (*swp\_3958*) was proven to have function in anaerobic nitrite reduction in WP3 (data not shown). In the mutant strain  $\Delta napA2$ , NapC (or maybe part of CymA also) is supposed to be able to fulfill the electron transfer function from quinol pool to NapA1B1, then CymA can transport freely available electrons to NrfA instantly after nitrate reduction to initiate nitrite reduction (Figure 8b). In the  $\Delta napC$  mutant, CymA should mediate the electron flow to NapAB, and then transfer electron to NrfA. As CymA is at the promiscuous place, the nitrite reduction is not as efficient as in the WT (Figure 8c). In the case of  $\Delta napA1$ , the electron flow from CymA to NapAB and then to NrfA was not been

influenced, and the function of NapA1 could be fully compensated by NapA2, thus the loss of *napA1* gene would not affect nitrate respiration (Figure 8d). We also observed that there was noticeable amount of nitrite generated in the culture of  $\Delta napC \Delta cymA$  mutant, which indicates that there is a third electron transport protein that has minor function in delivering the electrons to nitrite reductase. Different from *S. oneidensis* MR-1 that contains NapGH, no NapGH exist in WP3. We suppose that the protein TorC who also belongs to NapC/NirT protein family with similar function and structure, may take a minor function of NapC and CymA in WP3.

#### Why do most *Shewanella* contain two NAP systems?

As stated above, *Shewanella* is unique in having two sets of NAP systems, NAP- $\alpha$  with NapC and NAP- $\beta$  without NapC. In *E. coli*, NapC was proved to be able to transfer electrons from both ubiquinol and menaquinol pool and it was considered that the activity of the NapC-based complex (NAP- $\alpha$ ) or the NapGH-based complex (NAP- $\beta$ ) in *Shewanella* may

be directed by the composition of the available quinol pool, which may depend on the presence of oxygen (Simpson *et al.*, 2009). However, in our study, we found that both Nap- $\alpha$  and Nap- $\beta$  contribute to anaerobic nitrate respiration of WP3. No nitrite was detected when WP3 incubated under aerobic condition with the medium added with nitrate. Both systems were found induced by nitrate under anaerobic condition, but not expressed at aerobic condition with nitrate. Now the question arises, why does *Shewanella* contain NAP systems with similar functions in anaerobic respiration?

In nature, the substances that can be respired by bacteria are changing in the environment, and usually several electron acceptors are accessible to microbes at the same time. Therefore, it is quite possible that possessing a set of gene, which is dedicated to a certain type of substance, will confer a selective advantage to the organism. The *Shewanella* species are famous for their respiratory versatility, and the electron transport protein CymA participates in many pathways such as metal, dimethylsulfoxide, nitrate and nitrite reduction in the studied *Shewanella* (Murphy and Saltikov 2007). The NapC, which transfer electron to NapAB specifically, is a dedicated electron transport protein. In the case of WP3, CymA was proven to be shared by Fe<sup>3+</sup> reduction, nitrate and nitrite reduction (unpublished data and the present study). Therefore, containing both *napC* and *cymA* are better than containing *cymA* only. That is to say in nitrate ammonification electron transport to NapAB and NrfA by different transport protein could be more efficient than by a multi-functional protein only. Our data support the idea that *Shewanella* may use CymA as universal component for many electron transport pathways at beginning and obtained dedicated electron transfer proteins for some of these pathways with time (Gao *et al.*, 2009). This would explain why most of the *Shewanella* contain two *nap* operons.

#### *NAP- $\alpha$ is cold inducible*

Although both NAP systems in WP3 contribute to anaerobic nitrate respiration, and both are induced by nitrate anaerobically. It is very interesting to notice that the NAP- $\alpha$  genes are highly induced at low temperature (4 °C) comparing with those at its optimal growth temperature (20 °C), while the transcription of NAP- $\beta$  is relatively downregulated by low temperature (Figure 5). We also assessed the influence of high pressure to the nitrate respiration of WP3 (Wang *et al.*, 2008 and our unpublished microarray data), however the expression of the two NAPs was not changed under different pressures. The induction of NAP- $\alpha$  at low temperature suggests that NAP- $\alpha$  may benefit the nitrate respiration of WP3 in the cold environments. *Shewanella* species are renowned for their capability to thrive at cold conditions. At low temperature, most of the biochemistry reactions become slow. To cope with this,

cold living organisms may increase the concentrations of their enzymes, and/or improve their catalytic efficiencies at low temperature. Considering that NAP- $\alpha$  is a dedicated and more efficient nitrate reducing system, induction of NAP- $\alpha$  would be a wise strategy to respire nitrate at low temperature. We hypothesize that when WP3 lives at low temperature, it produces more NAP- $\alpha$  for more efficient energy production through nitrate respiration, as more free CymAs could be available to deliver electrons to NrfA for nitrite reduction. Therefore, it is an economic way to respire nitrate for energy production at cold conditions.

A binding motif for NarP was found in the upstream regions of all the NAP- $\alpha$  and NAP- $\beta$  of *Shewanella*, suggesting their expression control under the NarP two-component regulation system. However, no typical cold shock box sequence was found in the potential promoter regions of the NAP genes (unpublished data). Interestingly, a gene encoding a DEAD box RNA helicases: HrpA is always located in the upstream of the NAP- $\alpha$  operons of the *Shewanella* (except *S. denitrificans* and *S. frigidimarina*). It is possible that this HrpA protein may regulate the transcription and facilitate the mRNA processing of NAP- $\alpha$  at low temperature. Containing a cold inducible NAP- $\alpha$  may be a widely utilized strategy for *Shewanella* genus to thrive at low temperature.

#### *The evolution of two nap operons*

The phylogenetic analyses of NAP systems showed that horizontal gene transfer of the NAP systems has frequently occurred among bacteria and NAP- $\beta$  is a more ancient system in *Shewanella* than the Nap- $\alpha$ -1 and Nap- $\alpha$ -2 groups (Figures 1 and 2). The growth curve and the competition assay demonstrate that NAP- $\alpha$  confer a competition advantage to WP3 and possessing only Nap- $\alpha$  is better than possessing both NAP- $\alpha$  and NAP- $\beta$ , or NAP- $\beta$  only. Together with the fact that almost all *Shewanella* can use metal and many electron transport pathways share CymA as a common component. It is very likely that the CymA-dependent respiration system is more ancient. If it holds *S. oneidensis* MR-1, which only has NAP- $\beta$ , may possess a preliminary anaerobic respiration system, whereas *S. benthica* and *S. violacea*, which contain only NAP- $\alpha$  may represent a more evolved respiration system. *S. denitrificans* also contains a single NAP- $\alpha$ , but it doesn't contain *cymA*, its evolution process of respiration system may be different from most of the *Shewanella*. Here, we suppose whether the time is long enough for the NAP- $\beta$  of some *Shewanella*, which will be eliminated through the selection, and there are some facts to support our hypothesis. In the genome of *S. frigidimarina* whose NAP- $\beta$  is only comprised of *napAB*, and in *S. baltica*, *S. woodyi* and WP3 the NAP- $\beta$  is *napDAB*. Considering the cold inducible property of NAP- $\alpha$  in WP3, and the psychrophilic property of *S. benthica* and *S. violacea*, cold may be one of the selection powers to make this process happen.

In conclusion, we have shown that the NAP- $\alpha$  and NAP- $\beta$  systems in *S. piezotolerans* WP3 are both functional in anaerobic nitrate respiration. Both NapC and CymA are essential in electron transport for nitrate reduction. Containing two NAP systems in *Shewanella* genomes may be a reflection of the intermediate stage of evolution: it had a preliminary nitrate reduction system (NAP- $\beta$ ) sharing CymA with some other respiring systems at the beginning; then acquired a dedicated nitrate reducing system (NAP- $\alpha$ ) with time for more efficient nitrate utilization; would evolve to a single NAP- $\alpha$  at the next step of evolution. However, we cannot exclude the possibility that NAP- $\beta$  would be useful under certain conditions. Our study will give some hints for considering the evolution of other respiration systems in *Shewanella* and even in other bacteria, and will be very useful for the designed engineering of *Shewanella* for more efficient environmental bioremediation.

## Acknowledgements

This work has been partly supported by Natural Science Foundation of China (grant number 40625016, 40776095, 40876086), by the National High-Tech Program (2007AA091904), and by COMRA fund (DYXM-115-02-2-03).

## References

- Balch WE, Wolfe RS. (1976). New approach to the cultivation of methanogenic bacteria: 2-mercaptoethanesulfonic acid (HS-CoM)-dependent growth of *Methanobacterium ruminantium* in a pressurized atmosphere. *Appl Environ Microbiol* **32**: 781–791.
- Brondijk THC, Fiegen D, Richardson DJ, Cole JA. (2002). Roles of NapF, NapG and NapH, subunits of the *Escherichia coli* periplasmic nitrate reductase, in ubiquinol oxidation. *Mol Microbiol* **44**: 245–255.
- Brondijk THC, Nilavongse A, Filenko N, Richardson DJ, Cole JA. (2004). NapGH components of the periplasmic nitrate reductase of *Escherichia coli* K-12: location, topology and physiological roles in quinol oxidation and redox balancing. *Biochem J* **379**: 47–55.
- Cruz-Garcia C, Murray AE, Klappenbach JA, Stewart V, Tiedje JM. (2007). Respiratory nitrate ammonification by *Shewanella oneidensis* MR-1. *J Bacteriol* **189**: 656–662.
- Drummond AJ, Aston B, Buxton S, Cheung M, Heled J, Kearse M *et al.* (2010). Geneious v4.8. Available from <http://www.geneious.com>.
- Edwards RA, Keller LH, Schifferli DM. (1998). Improved allelic exchange vectors and their use to analyze 987P fimbria gene expression. *Gene* **207**: 149–157.
- Gao HC, Yang ZK, Barua S, Reed SB, Romine MF, Nealson KH *et al.* (2009). Reduction of nitrate in *Shewanella oneidensis* depends on atypical NAP and NRF systems with NapB as a preferred electron transport protein from CymA to NapA. *ISME J* **3**: 966–976.
- Gao HC, Yang ZK, Wu LY, Thompson DK, Zhou JZ. (2006). Global transcriptome analysis of the cold shock response of *Shewanella oneidensis* MR-1 and mutational analysis of its classical cold shock proteins. *J Bacteriol* **188**: 4560–4569.
- Gralnick JA, Vali H, Lies DP, Newman DK. (2006). Extracellular respiration of dimethyl sulfoxide by *Shewanella oneidensis* strain MR-1. *P Natl Acad Sci USA* **103**: 4669–4674.
- Gross R, Eichler R, Simon J. (2005). Site-directed modifications indicate differences in axial haem c iron ligation between the related NrfH and NapC families of multi-haem c-type cytochromes. *Biochem J* **390**: 689–693.
- Huelsenbeck JP, Ronquist F. (2001). MRBAYES: Bayesian inference of phylogenetic trees. *Bioinformatics* **17**: 754–755.
- Jepson BJ, Marietou A, Mohan S, Cole JA, Butler CS, Richardson DJ. (2006). Evolution of the soluble nitrate reductase: defining the monomeric periplasmic nitrate reductase subgroup. *Biochem Soc Trans* **34**: 122–126.
- Kern M, Simon J. (2008). Characterization of the NapGH quinol dehydrogenase complex involved in *Wolinella succinogenes* nitrate respiration. *Mol Microbiol* **69**: 1137–1152.
- Lenski RE, Rose MR, Simpson SC, Tadler SC. (1991). Long-term experimental evolution in *Escherichia coli*. I. Adaptation and divergence during 2,000 generations. *Am Naturalist* **138**: 1315–1341.
- Maillard J, Spronk CAEM, Buchanan G, Lyall V, Richardson DJ, Palmer T *et al.* (2007). Structural diversity in twin-arginine signal peptide-binding proteins. *P Natl Acad Sci USA* **104**: 15641–15646.
- McGinnis S, Madden TL. (2004). BLAST: at the core of a powerful and diverse set of sequence analysis tools. *Nucleic Acids Res* **32**: W20–W25.
- Miller TL, Wolin MJ. (1974). A serum bottle modification of the Hungate technique for cultivating obligate anaerobes. *Appl Microbiol* **27**: 985–987.
- Moreno-Vivian C, Cabello P, Martinez-Luque M, Blasco R, Castillo F. (1999). Prokaryotic nitrate reduction: molecular properties and functional distinction among bacterial nitrate reductases. *J Bacteriol* **181**: 6573–6584.
- Murphy JN, Saltikov CW. (2007). The *cymA* gene, encoding a tetraheme c-type cytochrome, is required for arsenate respiration in *Shewanella* species. *J Bacteriol* **189**: 2283–2290.
- Myers JM, Myers CR. (2000). Role of the tetraheme cytochrome CymA in anaerobic electron transport in cells of *Shewanella putrefaciens* MR-1 with normal levels of menaquinone. *J Bacteriol* **182**: 67–75.
- Pittman MS, Elvers KT, Lee L, Jones MA, Poole RK, Park SF *et al.* (2007). Growth of *Campylobacter jejuni* on nitrate and nitrite: electron transport to NapA and NrfA via NrfH and distinct roles for NrfA and the globin Cgb in protection against nitrosative stress. *Mol Microbiol* **63**: 575–590.
- Potter LC, Millington P, Griffiths L, Thomas GH, Cole JA. (1999). Competition between *Escherichia coli* strains expressing either a periplasmic or a membrane-bound nitrate reductase: does Nap confer a selective advantage during nitrate-limited growth? *Biochem J* **344**: 77–84.
- Richardson DJ, Berks BC, Russell DA, Spiro S, Taylor CJ. (2001). Functional, biochemical and genetic diversity of prokaryotic nitrate reductases. *Cell Mol Life Sci* **58**: 165–178.
- Sears HJ, Little PJ, Richardson DJ, Berks BC, Spiro S, Ferguson SJ. (1997). Identification of an assimilatory nitrate reductase in mutants of *Paracoccus denitrificans* GB17 deficient in nitrate respiration. *Arch Microbiol* **167**: 61–66.
- Simpson PJ, Richardson DJ, Codd R. (2010). The periplasmic nitrate reductase in *Shewanella*: the resolution,

- distribution and functional implications of two NAP isoforms, NapEDABC and NapDAGHB. *Microbiol* **156**: 302–312.
- Spector MP, del Portillo FG, Bearson SMD, Mahmud A, Magut M, Finlay BB *et al.* (1999). The *rpoS*-dependent starvation-stress response locus *stiA* encodes a nitrate reductase (*narZYWV*) required for carbon-starvation-inducible thermotolerance and acid tolerance in *Salmonella typhimurium*. *Microbiol-Uk* **145**: 3035–3045.
- Stewart V, Lu Y, Darwin AJ. (2002). Periplasmic nitrate reductase (NapABC enzyme) supports anaerobic respiration by *Escherichia coli* K-12. *J Bacteriol* **184**: 1314–1323.
- Stolz JF, Basu P. (2002). Evolution of nitrate reductase: molecular and structural variations on a common function. *Chembiochem* **3**: 198–206.
- Tabata A, Yamamoto I, Matsuzaki M, Satoh T. (2005). Differential regulation of periplasmic nitrate reductase gene (*napKFDABC*) expression between aerobiosis and anaerobiosis with nitrate in a denitrifying phototroph *Rhodobacter sphaeroides* f sp denitrificans. *Arch Microbiol* **184**: 108–116.
- Thompson JD, Plewniak F, Poch O. (1999). A comprehensive comparison of multiple sequence alignment programs. *Nucleic Acids Res* **27**: 2682–2690.
- Wang F, Li Q, Xiao X. (2007). A novel filamentous phage from the deep-sea bacterium *Shewanella piezotolerans* WP3 is induced at low temperature. *J Bacteriol* **189**: 7151–7153.
- Wang F, Xiao X, Ou HY, Gai YB, Wang FP. (2009). Role and regulation of fatty acid biosynthesis in the response of *Shewanella piezotolerans* WP3 to different temperatures and pressures. *J Bacteriol* **191**: 2574–2584.
- Wang FP, Wang JB, Jian HH, Zhang B, Li SK, Wang F *et al.* (2008). Environmental adaptation: genomic analysis of the piezotolerant and psychrotolerant deep-sea iron reducing bacterium *Shewanella piezotolerans* WP3. *PLoS One* **3**: e1937.
- Xiao X, Wang P, Zeng X, Bartlett DH, Wang FP. (2007). *Shewanella psychrophila* sp. nov. and *Shewanella piezotolerans* sp. nov., isolated from west pacific deep-sea sediment. *Int J Syst Evol Microbiol* **57**: 60–65.

Supplementary Information accompanies the paper on The ISME Journal website (<http://www.nature.com/ismej>)